

## Gold Pool Opening Service

### Pool Opening

Remove Safety cover or tarp  
Remove winter fitting and install summer fittings  
Install Paramount six-port Module, if needed  
Install ladder, step rails, and basketball goal, as needed  
Start system and evaluate operation  
Complete Equipment Checklist

### Pool Cleaning

POOL OPENING SERVICE INCLUDES: ■ Replace O-rings, gauges, and/or gasket, as needed ■ Vacuum dirt and debris, up to one hour ■ Brush pool walls and scrub water line ■ Net surface of pool water ■ Shock and algaecide are included

### Pump

Check for Proper operation/flow/circulation and adjust, if needed  
Check impeller and clean out debris, if needed  
Check all seals and replace, if needed

### Ball Valves

Check for proper function and notify if replacement is needed

### Filter

Change sand/Clean Cartridge Filter  
Check all Seals and replace, if needed  
Check Multit-port operation  
Check internal filter parts

### Chlorinator/Salt Cell

Check Operations and adjust, if needed  
Check and replace seals, if needed  
Clean salt cell  
Clean chlorinator strainer, if needed

### Heater

Check for proper operation and adjust, if needed  
Vacuum and blowout all debris from burners and heat exchangers  
Check for proper gas pressure  
Check for soot on heat exchanger and clean  
Check for any or all leaks and fix, if needed

### UV/O3

Check for proper function  
Check all seals and replace

### Auto cover

Clean debris out of auto cover box  
Cleaning of cover tracks  
Inspection and tightening of all hardware  
Evaluation of pulleys, sensors, sliders/gliders, and guides  
Replace of sliders/gliders, guides, and pulleys, if necessary  
Alignment and safety inspection of fabric and ropes  
Clean cover as needed, up to one hour

### Check for Settling of the Equipment Pad

If settling has occurred, check plumbing for excessive stress that may cause future issues and notify customer  
Blow out pool closing  
Winterize pump, salt cell, chlorinator, Ozonator, UV, heater, filter, as needed  
Winterize in-floor cleaning system, where applicable  
Winterize skimmer  
Winterize Returns  
Install tarp/safety cover